Item No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
6	Teakwood windows with battened shutters with ¾″ iron bars, etc., complete (shutters in four halves) as per specifications	S.ft.	1 6 0	32	
7	Teakwood work wrought and put up with two coats of wood oiling and tarring	C.ft.	5 6 0	31.14	
8	Roofing with 1st class Mangalore tiles on 2″×1″ teak reepers and eaves protected with a reaper ..	Sqr.	25 0 0	4.85	
9	Ridge tiles set in mortar	R.ft.	0 7 6	61	
10	Teakwood plain eave board 9″×1″ with painting ..	„	0 8 0	83	
11	Chunam plastering ¾″ thick	Sqr.	3 4 0	6.97	
12	Flooring with 1½″ to 2″ baby jelly cement concrete over 3″ lime concrete and cement mortar plastering ½″ including cutting lines mixed with red colour ..	„	20 0 0	1.48	
13	Pointing with cement	„	3 4 0	7.65	
14	Painting doors, windows, etc., with green paint manufactured at the Industrial Testing Laboratory—two coats	„	3 8 0	8.02	
15	Whitewashing 2 coats	„	0 4 0	6.97	
16	Supplying and fixing 1½″ G. I. drain pipes	Each	2 0 0	5	

M. K. NARASIMHA IYER,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 5th December 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 20th December 1939, for constructing Sylk pattern drains in Chikballapur Town for the year 1939-40. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 380 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for constructing Sylk pattern drains in Chikballapur Town for the year 1939--40," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Estimate for the approximate quantity for constructing Sylk pattern drains in Chikballapur Town for the year 1939-40.

Item No.	Description of work	Unit	Quantity
I	Constructing sylk pattern drains with new burnt stone slabs of 3″ thick in surki concrete bed of 3″ thick and forming a central channel portion with cement concrete 1 : 2 : 4 for sides and bottom over 1½″ thick cement concrete bed and surface plastered over with ½″ thick cement mortar including earthwork, etc., complete as per design—		
1	6″(3) sylk pattern drain	R.ft.	700
2	6″(2) do	,,	260
3	3″ do	,,	4,420
4	Constructing "L" pattern drains with new slabs of 3″ thick in surki concrete bed of 9″×4½″ and rounding of the centre portion with cement concrete and cement mortar plaster, etc., complete as per design	,,	670
5	Improving the existing box-drain by raising the bed with 3″ thick surki concrete and putting 1½″ thick cement concrete bed and forming the invert and plastering ½″ thick cement mortar including cement mortar pointing to the sidewalls, etc., complete as per design	,,	600
	Rates to the following items of works also to be quoted.		
6	Constructing sylk pattern drain of 3″ section with available slabs on 3″ thick surki concrete bed and forming an invert with cement concrete 1 : 2 : 4 over 1½″ thick bed of cement concrete including the dismantling of old drain splitting dressing conveying fixing and the surface plastered over with ½″ thick cement mortar, etc., complete as per design ..	R.ft.	..
7	New burnt stone in clay	C.ft.	..
8	Providing and fixing 6″ thick burnt stone slabs with rough dress ..	Sq.ft.	..
9	Cement mortar pointing	Sqr.	..
10	Do plaster ½″ thick (1 : 3)	,,	..
11	New size stone in mortar	C.ft.	..

K. S. HUTCHA RAO
Sanitary Engineer.

MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF AGRICULTURE.

OFFICE OF THE AGRICULTURAL ENGINEER, BANGALORE.

Notification No. '9 *of* 1939-40, *dated* 11*th December* 1939.

1. Notice is hereby given that sealed tenders will be received at the Office of the Agricultural Engineer, Bangalore, up to 2 P.M. on 29th December 1939 for sinking a well on the Cattle Breeding Station, Ajjampur, and improving the well on the Cattle Breeding Sub-Station, Basur, Kadur Taluk.

2. The approximate estimate of quantities for the above works are given below.

3. The quantities are not guaranteed. The works should be completed within one month from the date of acceptance of tender.

4. Earnest money of Rs. 70 and Rs. 30 in cash should be remitted under Revenue Deposit in the Kadur Taluk Treasury, or State Huzur Treasury, Bangalore, with a chellan duly filled in by the tenderer. The tenders should be superscribed 'Sinking a well on the Cattle Breeding Station, Ajjampur' or 'Improving the well on the Basur Sub-Station.' The tenders will be opened at 2-30 P.M. on 29th December 1939.

5. Subject to the formal sanction of the Director of Agriculture, the acceptance of tenders rest with the Agricultural Engineer, who does not bind himself to accept the lowest or any tender or assign any reason whatsoever for the rejection of any tender.

6. Within a week of the acceptance of the tender, the successful tenderers will be required to furnish a cash security of 5 per cent of the value of the work and to execute the usual contract bond in default of which their tenders will be considered as cancelled and the security deposits forfeited.

7. The name of the successful competitor whose tender has been accepted will be notified in due course.

8. After acceptance of the successful tender, the earnest money deposited on therefused tenders will be arranged to be returned to the parties.

9. Rates over tendered rates will on account be enhanced.

10. Quotations must be written both in words and figures.

11. The measurements checked by the Agricultural Engineer will have to be accepted as final.